




माडी नगरपालिका नगर कार्यपालिकाको कार्यालय

यसन्तपुर, चितवन
बागमती प्रदेश, नेपाल
२०७३

प.सं. ०८२/०८३
च.नं. ३०९८



मिति :- २०८३।०२।१३

विषय: दरभाउ पेश गर्ने सम्बन्धमा ।

श्री सबै फर्म तथा कम्पनीहरू,


..... ।

प्रस्तुत विषयमा यस माडी नगरपालिका वडा नं. ९ हनुमानझुलामा स्वास्थ्य संस्था सञ्चालन तथा व्यवस्थापन सम्बन्धी कार्य गर्नुपर्ने भएकोले यस पत्रसाथ संलग्न बिल अफ क्वान्टिटी (BOQ) मा उल्लिखित कार्यहरू के-कति दररेटमा गर्न सकिन्छ, ईच्छुक फर्म तथा कम्पनीहरूले तपसिल बमोजिमका कागजातहरू संलग्न गरी यो पत्रको मितिले ७(सात) दिन भित्र यस कार्यालयमा दरभाउ पेश गर्नुहुन अनुरोध छ ।

.....
(जगत प्रसाद भुसाल)
प्रमुख प्रशासकीय अधिकृत
जगत प्रसाद भुसाल
प्रमुख प्रशासकीय अधिकृत

तपसिल

१. फर्म तथा कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी- १ प्रति
२. आ.व. २०८२/०८३ को लागि नवीकरण भएको निर्माण व्यवसायी ईजाजतपत्रको प्रतिलिपी- १ प्रति
३. प्यान/भ्याट दर्ता प्रमाणपत्रको प्रतिलिपी- १ प्रति
४. आ.व. २०८१/०८२ को कर चुक्ता प्रमाणपत्रको प्रतिलिपी- १ प्रति
५. रितपूर्वक भरिएको Bill of Quantity (BOQ) - १ प्रति



MADI MUNICIPALITY
OFFICE OF MUNICIPAL EXECUTIVE
Basantapur, Madi, Chitwan

Bill of Quantity (BOQ)

कार्यक्रम: स्वास्थ्य संस्था संचालन तथा व्यवस्थापन

स्थान: माडी - ९, हनुमानगढुला

प्रमुख प्रशासकीय अधिकारी
पोसा

S.N.	Description of works	Unit	Quantity	Rate in figure	Rate in Words	Amount (NRs.)	Remarks
1.00	Excavation in all type of soil including disposal all complete as per specification,, all complete as per specification and Engineer's instruction.	cum	1.95				
2.00	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	0.61				
3.00	Plain cement Concrete (PCC) M10(1:3:6) for foundations with approved quality of cement, sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	cum	0.45				
4.00	Providing and laying hand mixed plain cement concrete of nominal mix 1:1.5:3 (1 cement : 1.5 sand :3 coarse aggregate) for leveling course in foundation and under floor of building etc in all level with brokenstone aggregate of size not more than 25mm of approved quality including formwork wherever necessary, dewatering, batching, mixing, transporting, placing, compacting, curing, including all lead and lift, etc., all complete as per drawing, specifications and the instructions of the engineer	cum	1.55				
5.00	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and specifications (60% M15 concrete and 40% boulder/ stones) using mechanical Aids.	cum	1.87				
6.00	Good quality local chimney made Brickwork in 1:4 CS mortar up to Ground floor in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	cum	3.54				
7.00	Plaster works, 12.5mm thick cement plaster work in 1:4 cement mortar on inner and outer wall with good finish including cleaning, wetting the surface and curing all complete.	sqm	23.04				
8.00	Colouring with 2 coats of weather coat of approved colour with primer Painting	sqm	23.04				
9.00	Glazed porcelain clay tiles in cement sand mortar (1:4) ratio with approved colour on wall and floor.	sqm	12.26				
10.00	Steel reinforcement bar of Fe 500 grade including straightening, cleaning, cutting, bending, placing in position and banding with annealed binding wire all complete as per design, drawing and specification.	kg	117.53				
11.00	Providing Formworks with local wood planks on slab and bands	sqm	12.07				
12.00	Supplying and Installation UPVC Door 100*60mm White Colour with Top and Bottom UPVC panel	sqm	2.78				
13.00	Supplying and fixing UPVC Casement window 60*60mm White glass with 5mm Glass	sqm	0.54				

MADI MUNICIPALITY
OFFICE OF MUNICIPAL ENGINEER
Basantapur, Madi, Chitwan



Bill of Quantity (BOQ)

कार्यक्रम: स्वास्थ्य संस्था संचालन तथा व्यवस्थापन

स्थान: माडी - ९, हनुमानचौला

S.N.	Description of works	Unit	Quantity	Rate in figure	Rate in Words	Amount (NRs.)	Remarks
14.00	CPVC Pipe (20mm) sdr 13.5 (22.5 kg/cm2) for watersupply and fitting works	rm	15.00				
15.00	PVC Pipe(110mm)-4kg/cm2	rm	3.00				
16.00	Supplying & Fixing 18" Ceramic Pan Set With Foot Rest	nos	1.00				
17.00	Supplying and fixing of hindware, sera, paryvare or equivalent commode complete set with jet spray	nos	1.00				
18.00	Supplying and fixing of simple 15mm cp bib cock short gun all complete	nos	2.00				
19.00	Supplying and fixing of 15mm pillar cock	nos	1.00				
20.00	Supplying and fixing of CPVC Equal Tee (20 mm)	nos	1.00				
21.00	Supplying and fixing of CPVC Coupler (20 mm)	nos	4.00				
22.00	Supplying and fixing of CPVC Union (20mm)	nos	4.00				
23.00	Supplying and fixing of CPVC Elbow 20mm	nos	3.00				
24.00	Supplying and fixing of CPVC End cap 20mm	nos	1.00				
25.00	Supplying and fixing of Stop Valve (20 mm)	nos	1.00				
26.00	Supplying and fixing of Looking Mirror 16" x 20"	nos	1.00				
27.00	Supplying and fixing of Hindare sera/ porcelain Glazed Wash Basin (20"x16")	set	1.00				
28.00	Supplying and fixing of 15mm Angle cock	nos	2.00				
29.00	Supplying and fixing of shower fancy	set	1.00				
30.00	Supplying and fixing of GI reducer Tee 40mm dia all complete	nos	1.00				
31.00	Supplying and fixing of GI nipple 9" long 32mm dia	nos	1.00				
32.00	Supplying and fixing of GI union 20mm dia	nos	1.00				
33.00	light point wiring work using 3/22 wire NS certified	point	2.00				
34.00	15 amp power point wiring work using 3/22 and 1/18 wire NS certified	rm	1.00				
35.00	Supplying and fixing of DC light 5w	nos	2.00				
36.00	Notice Board	LS	1.00				
	Sub Total						
	13% VAT						
	Grand Total						

Contractor's Name:

Address:

Signature:

Stamp:

Date: